



# JDRM Engineering, Inc.

5604 N. MAIN STREET, SUITE 200 + SYLVANIA, OHIO 43560 + PH. (419) 824-2400 + FAX (419) 824-2409

RIVERVIEW HEALTH CARE CAMPUS  
OTTAWA, COUNTY  
KITCHEN HOOD REPLACEMENT PROJECT  
8180 W. STATE ROUTE 163  
OAK HARBOR, OH 43449

## ADDENDUM NO. + 2

September 9, 2015

The following additions, alterations, deletions and/or clarifications shall be part of the Base Bid as much as if they were originally included in the Contract Documents.

### I. SPECIFICATIONS:

A. No changes at this time.

### II. DRAWINGS:

A. Drawing E-001: Legend, Specifications, Details (Drawing Not Reissued):

1. Contactors "CC-1" and "CC-2" are electrically held.

B. Drawing E-102: Partial First Floor Plans – Electrical – New Work (Drawing Not Reissued):

1. One of the three luminaires north of the kitchen hood interferes with the utensil rack. The utensil rack shall be relocated where directed by the Owner.
2. The two pull stations are Ansul system "cable release" pulls. Provide rough-in octagon boxes with 1/2" conduit to above ceiling.
3. The solenoid valves (symbol SV) in gas piping are controlled by the hood controls located in the "Utility Cabinet" furnished with the hood.

### III. GENERAL:

- A. The temporary partition to be installed in the Main Kitchen is to be double visqueen (one layer on each side).
- B. The work in the Pantry Area may take place prior or after the two week period of work associated with the replacement of the hood in the Main Kitchen.

END OF ADDENDUM NO. + 2