

OTTAWA COUNTY COURTHOUSE COMPLEX SIDEWALK PROJECT 2017

ADDENDUM #2

August 18, 2017

1. Page S-2 P 2. Should read: At #1 - S. Madison road crossing access ramp, curb cutout and tactile mat look fine, so the contractor would remove some of the existing concrete then re-pour and start our angle to the east to tie into the new North/South walk location. Pin to existing.
2. Page S-3 P 10. Should read: Remove concrete pedestal and concrete around it. Replace with topsoil and hydro-seed.
3. Page PI-3 Base Bid New Sheet.
4. Change on PI-5 Paragraph X. Concrete second paragraph should read:

Concrete will be: 4000 PSI minimum in 28 days; 0.45 water-cement ratio maximum; slump between 3-4 inches; air-cement ratio shall be $6.5\% \pm 1.5\%$; 3 pounds per yard of structural fiber of Forta-Ferro or equivalent for all concrete used on job site. Follow manufacturers recommendation's on mixing of fiber with concrete.

OTTAWA COUNTY COURTHOUSE COMPLEX SIDEWALK PROJECT 2017

BASE BID

	<u>ITEM</u>	<u>QTY</u>	<u>UNIT PRICE</u>	<u>PRICE</u>
1	Remove Concrete Pavement	13,220 Sq. Ft.	\$	\$
2	Excavation – Haul Spoils Off-Site	70 Cu. Yd.	\$	\$
3	#304 Base	290 Ton	\$	\$
4	Embankment	70 Cu. Yd.	\$	\$
5	Curb Ramp	400 Sq. Ft.	\$	\$
6	Topsoil Furnished & Placed	53 Cu. Yd.	\$	\$
7	Seeding and Mulching	375 Sq. Yd.	\$	\$
8	Mobilization	Lump		\$
9	Contract Bond	Lump		\$
10	Clean Out Pit	Lump		\$
11	Site Visit by Testing Firm At Owners Request for Concrete Slump and Test Cylinders	(3)	\$	\$
12	New 4” Concrete per specification	Per Sq. Ft.	\$	\$
13	New 6” Concrete per specification	Per Sq. Ft.	\$	\$

TOTAL BID INCLUDING ITEMS 1 – 13 ABOVE \$ _____

Written Number _____ Dollars

Alternate Price for 4” Concrete with no reinforcing deduct (\$ _____) per Sq. Ft.

Alternate price for 6” Concrete with no reinforcing deduct (\$ _____) per Sq. Ft.

Alternate price for 4” concrete with 6x6 – 10x10 wire matts only (no fiber) in lieu of macro-fiber add \$ _____ per Sq. Ft or deduct (\$ _____) per Sq. Ft.

Alternate price for 6” concrete with 6x6 – 10x10 wire matts only (no fiber) in lieu of macro-fiber add \$ _____ per Sq. Ft. or deduct (\$ _____) per Sq. Ft.